



भोपाल स्मारक अस्पताल एवं अनुसंधान केंद्र, भोपाल

BHOPAL MEMORIAL HOSPITAL & RESEARCH CENTRE

स्वास्थ्य अनुसंधान विभाग, स्वास्थ्य एवं परिवार कल्याण मंत्रालय, भारत सरकार

Department of Health Research, Ministry of Health and Family Welfare, Government of India

रायसेन बायपास रोड, भोपाल 462038 (म.प्र.), Raisen Bye Pass Road, Bhopal – 462038 (M.P.)

Phone + 91 755 2742212-16, Fax +91 755 2748809, Email : bmhrcbhopal@gmail.com,

website : www.bmhrc.org

NOTICE INVITING QUOTATION (NIQ) FOR CIVIL WORK AT COOLING TOWER - I & II

Ref. : Quotation No. BMHRC/ES/Quotation/Civil Work Cooling Tower/2018-19/005

Sealed quotation are invited from experienced agencies for Civil work at Cooling Tower I & II.

The item wise description of works is depicted in the price bid format (**Annexure-A**) on which the rates are to be quoted by the bidders.

1) **General Terms & Conditions :**

- 1) The bidders are advised to visit the site & assess the scope of work.
- 2) Duration of work completion : The entire work of Civil work at Cooling Tower I & II to be completed within 20 days from award of work to the successful bidder.
- 3) The agency shall be solely responsible for safe execution of works at site and indemnify BMHRC against any loss of property & any injuries sustained by the manpower or third parties during the execution of works.
- 4) 90% payment would be released to the agency against the completed works to the satisfaction of BMHRC. 10% value of works would be retained by BMHRC for a period of one year against the defect liabilities and would be released after one year on rectification of any defects arises during the defect liability period.
- 5) Award of work : The work order will be awarded to the lowest evaluated (L-1) bidder.
- 6) Price bid Format : The bidders shall quote their prices in the format as per **Annexure-A** with seal & authorized signatures of firm.

- 7) Quality of work : The agency shall execute the work to the best of quality standards & norms.
- 8) The bidders shall enclosed self attested copies of following documents.
 - a) Registration Certificate of Firm.
 - b) PAN Card/ GST Registration.
- 9) The work shall be executed without any disturbance to the routine patient services at BMHRC.
- 10) Sealed quotations to be submitted in the sealed Box, marked as "Quotation Box" kept in the Basement of Administration Block (Near Deptt. of Purchase), **latest by 05-09-2018 up to 2:00 PM** & quotation would be **opened on 05-09-2018 at 03:30 PM** in Conference Hall of BMHRC.

Seal & sign of bidder
(Acceptance of terms & conditions of quotation)

Director, BMHRC

FINANCIAL BID

Ref. : Quotation No. BMHRC/ES/Quotation/Civil Work Cooling Tower/2018-19/005

S. No.	Item	Unit	Qty.	Rate	Amount in (figures)	Amount in (Words)
1	Providing and laying in position cement concrete of specified grade excluding the cost of centring ,shuttering -All work upto plinth level : 1:4:8 (1Cement : 4 Coarse sand: 8 graded stone aggregate40 mm nominal size)	Cum	4.55			
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering- All work up to plinth level. 1:2:4 (1 Cement : 2 Coarse sand :4 graded stone aggregate 20 mm nominal size.	Cum	5.96			
3	Form Work UNDER 200 wide	Meter	46.54			
4	Providing and fixing 1st quality ceramic glazed wall tiles confirming to IS :15622, of approved make, in all colours,shades except burgundy, bottle green,black of any size as approved by Engineer-in Charge, in skirting,risers of steps and dados,over 12mm thick bed of cement mortar 1:3 (1 cement :3 coarse sand) and jointing with grey cement slurry @ 3.3kg/sqm including pointing in white cement mixed with pigment of matching shade complete.	Sqm	75.63			
5	Providing and laying Ceramic glazed floor tiles of size 300 x 300mm of 1st quality conforming to IS : 15622 of approved make in colours such as white ,Ivory,Grey, Fume Red Brown,laid on 20mm thick cement mortar 1:4 (1 Cement :4 Coarse sand),jointing with grey cement slurry @ 3.3kg/sqm including pointing the joints with white cement and matching pigment etc. complete.	Sqm	45.54			

S. No.	Item	Unit	Qty.	Rate	Amount in (figures)	Amount in (Words)
6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.	Kg	310.00			
7	Supply & laying Stone Soling	Cum	6.81			
8	Supply & Filling of stone Dust over Stone Soling	Cum	3.41			
	Sub Total =					
	Add GST 12%					
	Total =					

Say in Words Rs.

Place :

Name of Contractor.....

Date :

Seal & Signature of contractor