

## भोपाल स्मारक अस्पताल एवं अनुसंधान केंद्र

### BHOPAL MEMORIAL HOSPITAL & RESEARCH CENTRE

Department of Health Research, Ministry of Health and Family Welfare, Government of India

रायसेन बायपास रोड, भोपाल 462038 (म.प्र.), Raisen Bye Pass Road, Bhopal – 462038 (M.P.)

Phone + 91 755 2742212-16, Fax +91 755 2748809, Email : [bmhrcbhopal@gmail.com](mailto:bmhrcbhopal@gmail.com), website : [www.bmhrc.org](http://www.bmhrc.org)

## Corrigendum Notice

**Ref. : Notice Inviting Quotation (NIQ) for Civil Work at Cooling Tower.**

**Quotation No. BMHRC/Quotation/Civil Work/Cooling Tower/2018-19/005.**

All the bidders are informed that in the Financial Bid of reference Notice Inviting Quotation posted in BMHRC website on 24-08-2018 following mentioned amendment has been made.

#### **Inclusion of an Item:**

S. No.	Item	Unit	Qty.
7	Providing and laying water proofing treatment on walls & bottom surface of water tank by applying cement slurry mixed with water proofin cement compound consisting of applying : a) First layer of slurry of cement @ 0.488 Kg/sqm mixed with water proofing cement compound @0.253kg/sqm. This layer is allowed to air cure for 4 hours. b) Second layer of slurry of cement @ 0.242 Kg/sqm mixed with water proofing cement compound @0.126 kg/sqm. This layer is allowed to air cure for 4 hours followed with water curing for 48 hrs. The rate includes preparation of surface, treatment and sealing of all joints, corners, junctions of pipes and masonry with polymer mixed slurry..	Sqm	121.17

The prospective bidders shall quote their rates on Revised Financial Bid Format of Notice Inviting Quotation appended herewith.

The deadline for submission of sealed quotation of Notice Inviting Quotation has been extended till **10-09-2018 upto 2:00 PM.**

**Dy. Director,  
Engineering Services,  
BMHRC, Bhopal**

**REVISED FINANCIAL BID**

[Submission latest by 10-09-2018 up to 2:00 PM & quotation would be opened on 10-09-2018 at 03:30 PM]

Ref. : Quotation No. BMHRC/ES/Quotation/Civil Work Cooling Tower/2018-19/005

S. No.	Item	Unit	Qty.	Rate	Amount in (figures)	Amount in (Words)
1	Providing and laying in position cement concrete of specified grade excluding the cost of centring ,shuttering -All work upto plinth level : 1:4:8 (1Cement : 4 Coarse sand: 8 graded stone aggregate40 mm nominal size)	Cum	4.55			
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering- All work up to plinth level. 1:2:4 (1 Cement : 2 Coarse sand :4 graded stone aggregate 20 mm nominal size.	Cum	5.96			
3	Form Work UNDER 200 wide	Meter	46.54			
4	Providing and fixing 1st quality ceramic glazed wall tiles confirming to IS :15622, of approved make, in all colours,shades except burgundy, bottle green,black of any size as approved by Engineer-in Charge, in skirting,risers of steps and dados,over 12mm thick bed of cement mortar 1:3 (1 cement :3 coarse sand) and jointing with grey cement slurry @ 3.3kg/sqm including pointing in white cement mixed with pigment of matching shade complete.	Sqm	75.63			
5	Providing and laying Ceramic glazed floor tiles of size 300 x 300mm of 1st quality conforming to IS : 15622 of approved make in colours such as white ,Ivory,Grey, Fume Red Brown,laid on 20mm thick cement mortar 1:4 (1 Cement :4 Coarse sand),jointing with grey cement slurry @ 3.3kg/sqm including pointing the joints with white cement and matching pigment etc. complete.	Sqm	45.54			

S. No.	Item	Unit	Qty.	Rate	Amount in (figures)	Amount in (Words)
6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.	Kg	310.00			
7	Providing and laying water proofing treatment on walls & bottom surface of water tank by applying cement slurry mixed with water proofin cement compound consisting of applying : a) First layer of slurry of cement @ 0.488 Kg/sqm mixed with water proofing cement compound @0.253kg/sqm. This layer is allowed to air cure for 4 hours. b) Second layer of slurry of cement @ 0.242 Kg/sqm mixed with water proofing cement compound @0.126 kg/sqm. This layer is allowed to air cure for 4 hours followed with water curing for 48 hrs. The rate includes preparation of surface, treatment and sealing of all joints, corners, junctions of pipes and masonry with polymer mixed slurry..	Sqm	121.17			
8	Supply & laying Stone Soling	Cum	6.81			
9	Supply & Filling of stone Dust over Stone Soling	Cum	3.41			
	<b>Sub Total =</b>					
	<b>Add GST 12%</b>					
	<b>Total =</b>					

Say in Words Rs. ....

Place :

Name of Contractor.....

Date :

Seal & Signature of contractor