



भोपाल स्मारक अस्पताल एवं अनुसंधान केंद्र, भोपाल

BHOPAL MEMORIAL HOSPITAL & RESEARCH CENTRE

स्वास्थ्य अनुसंधान विभाग, स्वास्थ्य एवं परिवार कल्याण मंत्रालय, भारत सरकार

Department of Health Research, Ministry of Health and Family Welfare, Government of India

रायसेन बायपास रोड, भोपाल 462038 (म.प्र.), Raisen Bye Pass Road, Bhopal – 462038 (M.P.)

Phone + 91 755 2742212-16, Fax +91 755 2748809, Email : bmhrcbhopal@gmail.com, website : www.bmhrc.org

NOTICE INVITING QUOTATION (NIQ) FOR RE-FLOORING OF SETTLED FLOORS AT RESIDENTIAL AREA.

Ref. : BMHRC/Quotation/Civil/Re-flooring/2018-19/10.

Sealed quotation is invited from experienced agencies for Re-Flooring of Settled Floors at Residential Area at BMHRC.

The item wise description of works is depicted in the price bid format (**Annexure-A**) on which the rates are to be quoted by the bidders.

1) General Terms & Conditions:

- 1) The bidders are advised to visit the site & assess the scope of work.
- 2) Duration of work completion : The entire work of Re-Flooring of Settled Floors at Residential Area at BMHRC is to be completed within 30 days from award of work to the successful bidder.
- 3) The agency shall be solely responsible for safe execution of works at site and indemnify BMHRC against any loss of property & any injuries sustained by the manpower or third parties during the execution of works.
- 4) Award of work : The work order will be awarded to the lowest evaluated (L-1) bidder.
- 5) Price bid Format : The bidders shall quote their prices in the format as per **Annexure-A** with seal & authorized signatures of firm.
- 6) Quality of work : The agency shall execute the work as per CPWD specifications.
- 7) The bidders shall enclosed self attested copies of following documents.
 - a) Registration Certificate of Firm.
 - b) PAN Card & GST Registration.
- 8) The work shall be executed without any disturbance to the routine patient services at BMHRC.
- 9) Payment Terms : The payment would be released to the agency within 45 days after completion of work and submission of invoice after deduction of taxes and statutory dues as applicable.
- 10) Security Retention : An amount @5% value of works would be deducted from the Bill of agency and withhold till the duration of defect liability period of one year. After the completion of Defect Liability Period and rectification of notified defects, the retention amount would be released to the agency.
- 11) The selected agency has to commence the work at site within 15 days of issue of the work order, in case of failure by the agency to start the works within the said duration BMHRC may cancel the work order and blacklist the agency for 3 years from participating in the work tenders/ quotations.
- 12) Sealed quotations to be submitted in the sealed Box, marked as "Quotation Box" kept in the Basement of Administration Block (Near Deptt. of Purchase), **latest by 30-10-2018 up to 2:00 PM** & quotation would be **opened on 30-10-2018 at 03:30 PM** in Conference Hall of BMHRC.

**Seal & sign of bidder
(Acceptance of terms & conditions of quotation)**

Director, BMHRC

FINANCIAL BID

Quotation No. : BMHRC/Quotation/Civil/Re-flooring/2018-19/10.
Abstract of Re- Flooring of Settled Floors at Residential Area

S. No.	DSR Code	Item	Unit	Qty.	Rate in Rs.	Amount In figures (RS.)	Amount in Words
1	15.2.1	Demolishing mosaic flooring & cement concrete including disposal of material with in 50 mtrs. Lead :					
		(D.S.R Item 15.2.1)	Cum	8.99			
2	15.60	Disposal of building rubbish/ malba/similar unserviceable, Dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved Municipal dumping ground or as approved by Engineer -in- charge,beyond 50 m initial lead, for all leads including all lifts involved.					
		Item 15.60	Cum	8.99			
3	2.1	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on Plan including disposal of excavated earth upto 50 m and Lift upto 1.5 m,disposed soil to be levelled and neatly dressed :					
		All kinds of soil	100 Sqm	59.95			
4	2.27	Supplying & filling in plinth with Jamuna Sand under floors , including watering, ramming, consolidating and dressing Complete.	Cum	8.99			
5	4 1 10	Providing & laying in position cement concrete of specified grade excluding the cost of centring and shuttering – All work upto plinth level.					
		01:05:10 (Item No. 4.1.10)	Cum	6.00			
6	5 1 3	Providing & laying in position specified grade of reinforced cement concrete excluding the cost of centring, shuttering, finishing and reinforcement. All work upto plinth level 1:2:4 (Item No. 5.1.3)	Sqm	6.00			
7	11 41	Providing & laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS : 15622, of approved make, in all colours and shades laid on 20mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), including grouting the joints with white Cement and matching pigments etc.,complete.					
	11. 41. 2	Size of the tile 600 x 600 mm	Sqm	59.95			

S. No.	DSR Code	Item	Unit	Qty.	Rate in Rs.	Amount In figures (RS.)	Amount in Words
8	11 46	Providing & laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS : 15622, of approved make, in all colours and shades, in skirting, riser of steps, over 12mm thick bed of cement mortar 1:3 (1 cement : 3 Coarse sand), including grouting the joints with white Cement and matching pigments etc., complete.					
	11.46.2	Size of the tile 600 mm x 600 mm	Sqm	8.33			
9	5 22 4	Reinforcement for R.C.C work including straightening cutting, bending, placing in position and binding all Complete.					
		Hot rolled deformed bars	Kg	500.00			
Sub Total =							
GST 12%							
Total =							

Amount In Words

Seal & Signature of Agency/Contractor

Date :

Place :